



South Dakota Department of Transportation
Division of Operations
700 E. Broadway Avenue
Pierre, South Dakota 57501-0286

October 2, 2026

Mr. Craig Smith
Director of Operations
South Dakota Department of Transportation
700 E. Broadway Avenue
Pierre, SD 57501

Subject: Construction Change Orders Report

Construction Change Orders (CCOs) completed in September contain an increase of \$811,923.39. Over the past 12 months, the total change to the original contract amounts has increased by 1.56%.

The following projects have a CCO with a change of more than \$100,000 or a change of more than 25.0% to the contract.

ABERDEEN REGION

1. Project: NH-P 0011(317), Brown, Day, Edmunds, Marshall, & McPherson, PCN 09KV
Location: Various locations in the Aberdeen area
Contractor: Bituminous Paving, Inc.
Type of Work: Asphalt surface treatment

Original Contract Amount:	\$	5,193,497.05
\$ Change on CCO No. 2:	\$	(277,865.50)
% Change on CCO No. 2:		5.4%
Net Change to Date:	\$	(277,310.50)

Explanation of Change on CCO No. 2: This decrease is the result of SDDOT adjusting contract quantities to match as built quantities normal for a surface treatment project.

2. Project: NH-P 0011(321), Brown, Day, Edmunds, Faulk, McPherson, & Potter County, PCN 09WL
 Location: Various locations in the Aberdeen area
 Contractor: Jensen Rock & Sand, Inc.
 Type of Work: Asphalt surface treatment

Original Contract Amount:	\$	3,815,497.08
\$ Change on CCO No. 2:	\$	(127,402.54)
% Change on CCO No. 2:		3.3%
Net Change to Date:	\$	(127,402.54)

Explanation of Change on CCO No. 2: This decrease is the result of SDDOT adjusting contract quantities to match as built quantities normal for a surface treatment project.

MITCHELL REGION

3. Project: IM 0020(186), Lincoln & Minnehaha County, PCN 06FV
 Location: Various locations in the Mitchell region
 Contractor: BX Civil & Construction, Inc.
 Type of Work: Shoulder strengthening, berm repair, bridge deck polymer chip seal, approach slab, approach pavement

Original Contract Amount:	\$	4,204,503.00
\$ Change on CCO No. 4:	\$	174,034.92
% Change on CCO No. 4:		4.1%
Net Change to Date:	\$	183,234.92

Explanation of Change on CCO No. 4: This increase is the result of SDDOT modifying guardrail layout to replace high tension guardrail with Type 1 MGS guardrail for safety purposes as well as adjusting plans quantities to match as built quantities.

4. Project: P 0042(77)301, Davison, Hanson, & McCook County, PCN 04F6
 Location: SD42 from SD37 to Bridgewater
 Contractor: Duininck, Inc.
 Type of Work: Cold milling, asphalt concrete resurfacing, pipe work

Original Contract Amount:	\$	10,389,694.55
\$ Change on CCO No. 8:	\$	(323,305.06)
% Change on CCO No. 8:		3.1%
Net Change to Date:	\$	(25,551.71)

Explanation of Change on CCO No. 8: This decrease is the result of SDDOT adjusting contract quantities to match as built quantities due to normal project variations and removing unnecessary items from the contract.

PIERRE REGION

5. Project: NH-P 0031(57), Haakon, Jackson, & Stanley County, PCN 095A
 Location: Various locations throughout the Pierre area
 Contractor: A-G-E Corporation
 Type of Work: Pipe work

Original Contract Amount:	\$	3,750,258.53
\$ Change on CCO No. 2:	\$	158,974.62
% Change on CCO No. 2:		4.2%
Net Change to Date:	\$	178,699.04

Explanation of Change on CCO No. 2: This increase is the result of SDDOT adjusting the contract to change the required work of 3 large concrete pipe culvert sizes from a cured in place pipe liner to a spray applied pipe liner. Additionally, the spray applied liner was added at a new location not originally included in the plans.

RAPID CITY REGION

6. Project: IM-B-TA 1902(67)0, Pennington County, PCN 065K
 Location: I-90 from north of Anamosa Street to North Street
 Contractor: Heavy Constructors, Inc.
 Type of Work: Replace structure, approach grading, PCC surfacing, concrete barrier, approach slabs, guardrail, lighting

Original Contract Amount:	\$	10,579,709.97
\$ Change on CCO No. 7:	\$	162,149.27
% Change on CCO No. 7:		1.5%
Net Change to Date:	\$	171,443.01

Explanation of Change on CCO No. 7: This increase is the result of SDDOT adjusting the contract quantities for pavement marking to include reinstalling markings that had to be moved to accommodate two-way traffic on the project.

7. Project: P 0042(103), Perkins County, PCN 09WY
Location: Various locations in the Belle Fourche area
Contractor: Highway Improvement, Inc.
Type of Work: Crack sealing, rout & seal

Original Contract Amount:	\$	267,824.25
Change on CCO No. 2:	\$	234,524.35
% Change on CCO No. 2:		87.6%
Net Change to Date:	\$	255,550.00

Explanation of Change on CCO No. 2: This increase is the result of SDDOT adjusting contract quantities of asphalt crack leveling to match as built quantities. Between the initial design inspection prior to the department preparing final plans and the start of construction, additional transverse cracks became depressed resulting in the need for full depth crack leveling instead of asphalt concrete crack sealant.

Sincerely,
Ryan K. Johnson
Senior Specification Engineer